



**TEST REPORT**

**Report No.:** F7657.02-550-44

**Rendered to:**

ALTECH PANEL SYSTEMS, LLC  
Cartersville, Georgia

**PRODUCT TYPE:** Metal Wall Panel System  
**SERIES/MODEL:** Low Profile Accu-Trac System DS without Stiffeners

<b>Title</b>	<b>Summary of Results</b>
Design Pressure	±2395 Pa (±50.00 psf)
Air Infiltration	<0.1 L/s/m <sup>2</sup> (<0.01 cfm/ft <sup>2</sup> )
Water Penetration Resistance Test Pressure	360 Pa (7.50 psf)
Uniform Load Structural Test Pressure	±3593 Pa (±75.00 psf)

Reference must be made to Report No. F7657.02-550-44, dated 06/13/16 for complete test specimen description and detailed test results.

**1.0 Report Issued To:** Altech Panel Systems, LLC  
1 Johnson Street, #118  
Cartersville, Georgia 30120

**2.0 Test Laboratory:** Architectural Testing, Inc., an Intertek company ("Intertek-ATI")  
1701 Westfork Drive, Suite 106  
Lithia Springs, Georgia 30122  
770-941-6916

**3.0 Project Summary:**

**3.1 Product Type:** Metal Wall Panel System

**3.2 Series/Model:** Low Profile Accu-Trac System DS without Stiffeners

**3.3 Compliance Statement:** Results obtained are tested values and were secured by using the designated test method(s). Test specimen description and results are reported herein.

**3.4 Test Date(s):** 04/18/16

**3.5 Test Record Retention End Date:** All test records for this report will be retained until April 19, 2020.

**3.6 Test Location:** Intertek-ATI test facility in Lithia Springs, Georgia.

**3.7 Test Specimen Source:** The test specimen(s) was provided by the client. Representative samples of the test specimen(s) will be retained by Intertek-ATI for a minimum of four years from the test completion date.

**3.8 Drawing Reference:** The test specimen drawings have been reviewed by Intertek-ATI and are representative of the test specimen(s) reported herein. Test specimen construction was verified by Intertek-ATI per the drawings located in Appendix C. Any deviations are documented herein or on the drawings.

### 3.9 List of Official Observers:

<u>Name</u>	<u>Company</u>
Doug McIntyre	Altech Panel Systems, LLC
Joel Ivey	Intertek-ATI
Ian McKenzie	Intertek-ATI
JP McDonald	Intertek-ATI

### 4.0 Test Method(s):

ASTM E283-04 (2012), *Test Method for Determining Rate of Air Leakage Through Exterior Windows, Curtain Walls and Doors Under Specified Pressure Differences Across the Specimen*

ASTM E330/E330M-14, *Test Method for Structural Performance of Exterior Windows, Doors, Skylights and Curtain Walls by Uniform Static Air Pressure Difference*

ASTM E331-00 (2009), *Test Method for Water Penetration of Exterior Windows, Skylights, Doors, and Curtain Walls by Uniform Static Air Pressure Difference*

### 5.0 Test Specimen Description:

#### 5.1 Product Sizes:

Overall Area: 8.9 m <sup>2</sup> (96.0 ft <sup>2</sup> )	Width		Height	
	millimeters	inches	millimeters	inches
Overall size	3658	144	2438	96
Top Left Panel TB2-06	914	36	876	34-1/2
Bottom Left Panel TB2-05	914	36	1518	59-3/4
Top Right Panel TB2-08	2702	106-3/8	876	34-1/2
Bottom Right Panel TB2-07	2702	106-3/8	1518	59-34

## 5.0 Test Specimen Description: (Continued)

### 5.2 Frame Construction:

Frame Member	Description
Perimeter support frame	Four C8 x 11.5 A36 C-channels
Bracing	One Bracing placed from frame end to frame end.
Bracing Brackets	Nine Bracing Brackets are placed between the stud and the brace.
End/Intermediate Studs	Ten total – 6" x 96" x 33 Ksi Steel studs. One on each end spaced 15-1/4" from the others and eight spaced at 16" on center.
Sheathing	5/8" DensGlas sheathing to Studs with screws 8" on center
Bottom Track	6" bottom track
Top Track	6" top track
Reveal	1/2" wide x 3/4" deep with accent strips
J-LP	Starter "J" extrusion at the bottom of the system. Fastened to steel stud through the sheathing via #12-14 Tek fasteners
F-LP	Shop attached to perimeter of all panels
MM-LP	Siding termination clip on the sides and head of system installed into key of F-LP extrusion. F-LP attached to framing via #12-14 Tek fasteners.
M-LP	Sliding attachment clip at the joints installed into key of F-LP extrusion (Section 2 of DWG# D01)

### 5.3 Panel Construction:

Panel Member	Material	Description
External Skin	Aluminum	4mm (0.157 in.) Aluminum Composite Material Panel

**6.0 Installation:**

<b>Location</b>	<b>Anchor Description</b>
Panels to Sheathing to Stud	The panels are secured to the sheathing using a sliding termination clip extrusion (MM-LP). The MM-LP Extrusion was fastened with #12-14 x 3/4" Tek screws every 16". Plastic Shims were placed in between every Tek fastener and silicone was placed around the frame edge. Sheathing was attached to studs using #6 self-tapping screws spaced 8" vertically and 16" on center horizontally.

**7.0 Test Results:** The temperature during testing was 26°C (78°F). The results are tabulated as follows:

Title of Test	Results	Allowed	Note
<b>Air Leakage,</b> per ASTM E283 at 75 Pa (1.57 psf)	<0.1 L/s/m <sup>2</sup> (<0.01 cfm/ft <sup>2</sup> )	1.5 L/s/m <sup>2</sup> (0.3 cfm/ft <sup>2</sup> ) max.	1
<b>Water Penetration,</b> per ASTM E331 at 360 Pa (7.50 psf)	Pass	No leakage	
<b>Uniform Load Deflection,</b> per ASTM E330 Deflections taken at perimeter +2395 Pa (+50.00 psf) -2635 Pa (-55.00 psf)	3.3 mm (0.13") 3.8 mm (0.15")	15.5 mm (0.61") max. 15.5 mm (0.61") max.	2, 3
<b>Uniform Load Deflection,</b> per ASTM E330 Deflections taken at span on of Panel TB1-03 +2395 Pa (+50.00 psf) -2635 Pa (-55.00 psf)	0.5 mm (.02") 0.2 mm (.01")	44.7 mm (1.76") max. 44.7 mm (1.76") max.	2, 3
<b>Uniform Load Structural,</b> per ASTM E330 Permanent sets taken at Perimeter +3593 Pa (+75.00 psf) -3952 Pa (-82.50 psf)	0.3 mm (0.03") 0.1 mm (0.04")	Report Only	2, 3
<b>Uniform Load Structural,</b> per ASTM E330 Permanent sets taken at span of Panel TB1-03 +3593 Pa (+75.00 psf) -3952 Pa (-82.50 psf)	0.4 mm (0.01") 0.2 mm (0.01")	Report Only	2, 3

## 7.0 Test Results: (Continued)

**General Note:** *All testing was performed in accordance with the referenced standard(s).*

*Note 1: Test Date 04/18/16 / Time: 7:30 AM*

*Note 2: Loads were held for 30 seconds.*

*Note 3: Tape was used to seal against air leakage during structural testing. In our opinion, the tape did not influence the results of the test.*

Intertek-ATI will service this report for the entire test record retention period. Test records such as detailed drawings, datasheets, representative samples of test specimens, or other pertinent project documentation, will be retained by Intertek-ATI for the entire test record retention period.

This report does not constitute certification of this product nor an opinion or endorsement by this laboratory. It is the exclusive property of the client so named herein and relates only to the specimen(s) tested. This report may not be reproduced, except in full, without the written approval of Intertek-ATI.

For ARCHITECTURAL TESTING, INC.:

---

Ian J. McKenzie  
Regional Manager

---

JP McDonald, P.E.  
Director – Regional Operations

IJM:jab

Attachments (pages): This report is complete only when all attachments listed are included.


Appendix A: Location of air seal (1)

Appendix B: Photograph(s) (1)

Appendix C: Drawings (7)

### Appendix A

**Location of Air Seal:** The air seal between the test specimen and the test wall is detailed below. The seal is made of foam weatherstripping and is attached to the edge of the test specimen buck. The test specimen buck is placed against the test wall and clamped in place, compressing the weatherstripping and creating a seal.



**Appendix B**

**Photograph**




**Photo No. 1**  
**Test Unit**

## **Appendix C**

### **Drawings**





NOTE: DRAWINGS MARKED "APPROVED" OR "FURNISH AS CORRECTED" WILL BE INTERPRETED AS AUTHORIZATION FOR FABRICATION.

This Drawing is the property of ALTECH PANEL SYSTEMS and shall be returned upon completion of work. Use or copy is permitted by contract only. Unauthorized use will be prosecuted.


SHEET INFORMATION:

ELEVATION VIEWS

PROJECT  
**TEST BUCKS**  
JOB NAME  
  
ARCH:  
ARCH


CUSTOMER  
**ALTECH PANEL SYSTEMS**

JOB NO.  
XX-XXXX  
CHECKED  
DWG  
DATE  
6/23/15  
DRAWN  
CAW  
DWG. NO.  
E01



1 TEST BUCK FRAMING  
E01 1 1/2" = 1'-0"


**Intertek**  
 Architectural Testing  
**Building Better Together.**  
 Test sample complies with these details.  
 Deviations are noted.  
 Report #: F7657.02-550-44 Date: 06/13/16  
 Verified by: 

  
 PH. (878) 721-4569  
 FAX (878) 721-4988  
 1 JOHNSON ST. · SUITE 118,  
 CARTERSVILLE, GA. 30120  
 WEBSITE: WWW.ALTECHPANEL.COM

NOTE: DRAWINGS MARKED "APPROVED" OR "FURNISH AS CORRECTED" WILL BE INTERPRETED AS AUTHORIZATION FOR FABRICATION.

This Drawing is the property of ALTECH PANEL SYSTEMS and shall be returned upon completion of work. Use or copy is permitted by contract only. Unauthorized use will be prosecuted.

SHEET INFORMATION:

ELEVATION VIEWS

PROJECT


**TEST BUCKS  
JOB NAME**

ARCH:  
ARCH



CUSTOMER

**ALTECH PANEL SYSTEMS**

JOB. NO.	XX-XXXX
CHECKED	DWG
DATE	6/23/15
DRAWN	CAW
DWG. NO.	E02



2  
 E02 TEST BUCK PANEL LAYOUT – ES WITH STIFFENERS  
 1 1/2"=1'-0"



3  
E03 TEST BUCK PANEL LAYOUT - DS NO STIFFENERS  
1 1/2" = 1'-0"

NOTE: DRAWINGS MARKED "APPROVED" OR "FURNISH AS CORRECTED" WILL BE INTERPRETED AS AUTHORIZATION FOR FABRICATION.

This Drawing is the property of ALTECH PANEL SYSTEMS and shall be returned upon completion of work. Use or copy is permitted by contract only. Unauthorized use will be prosecuted.

SHEET INFORMATION:

ELEVATION VIEWS

PROJECT


TEST BUCKS  
JOB NAME

ARCH:  
ARCH


CUSTOMER

ALTECH PANEL SYSTEMS


JOB. NO.	XX-XXXX
CHECKED	DWG
DATE	6/23/15
DRAWN	CAW
DWG. NO.	E03




1 BASE DETAIL FOR ES  
D01 1'-0"=1'-0"




2 JOINT DETAIL FOR ES  
D01 1'-0"=1'-0"



3 TOP DETAIL FOR ES  
D01 1'-0"=1'-0"



4 SIDE DETAIL FOR ES  
D01 1'-0"=1'-0"



NOTE: DRAWINGS MARKED "APPROVED" OR "FURNISH AS CORRECTED" WILL BE INTERPRETED AS AUTHORIZATION FOR FABRICATION.

This Drawing is the property of ALTECH PANEL SYSTEMS and shall be returned upon completion of work. Use or copy is permitted by contract only. Unauthorized use will be prosecuted.

SHEET INFORMATION:

LINE 2  
COVER SHEET

PROJECT

TEST BUCKS  
JOB NAME

ARCH:  
ARCH

CUSTOMER

ALTECH PANEL SYSTEMS

JOB NO. XX-XXXX  
CHECKED  
DATE 6/23/15  
DRAWN CAW  
DWG. NO. D01

NOTE: DRAWINGS MARKED "APPROVED" OR "FURNISH AS CORRECTED" WILL BE INTERPRETED AS AUTHORIZATION FOR FABRICATION.

This Drawing is the property of ALTECH PANEL SYSTEMS and shall be returned upon completion of work. Use or copy is permitted by contract only. Unauthorized use will be prosecuted.


SHEET INFORMATION:

LINE 2  
 COVER SHEET


PROJECT  
**TEST BUCKS**  
 JOB NAME  
 ARCH:  
 ARCH

CUSTOMER  
**ALTECH PANEL SYSTEMS**


JOB NO.  
 XX-XXXX  
 CHECKED  
 DWG  
 DATE  
 6/23/15  
 DRAWN  
 CAW  
 DWG. NO.  
 D02




1 BASE DETAIL FOR DS  
 D02 1'-0"=1'-0"




2 JOINT DETAIL FOR DS  
 D02 1'-0"=1'-0"



3 TOP DETAIL FOR DS  
 D02 1'-0"=1'-0"




4 SIDE DETAIL FOR DS  
 D02 1'-0"=1'-0"



1 SECTION DETAIL FOR DS AND ES  
 D03 1'-0"=1'-0"


  
**Building Better Together.**  
 Test sample complies with these details.  
 Deviations are noted.  
 Report #: **F7657.02-550-44** Date: **06/13/16**  
 Verified by: 

  
 PH. (878) 721-4569  
 FAX (878) 721-4988  
 1 JOHNSON ST. SUITE 118,  
 CARTERSVILLE, GA. 30120  
 WEBSITE: WWW.ALTECHPANEL.COM

NOTE: DRAWINGS MARKED "APPROVED" OR "FURNISH AS CORRECTED" WILL BE INTERPRETED AS AUTHORIZATION FOR FABRICATION.

This Drawing is the property of ALTECH PANEL SYSTEMS and shall be returned upon completion of work. Use or copy is permitted by contract only. Unauthorized use will be prosecuted.

SHEET INFORMATION:

LINE 2  
 COVER SHEET

PROJECT  
**TEST BUCKS**  
 JOB NAME  
 ARCH:  
 ARCH

CUSTOMER  
**ALTECH PANEL SYSTEMS**

JOB. NO. XX-XXXX  
 CHECKED DWG  
 DATE 6/23/15  
 DRAWN CAW  
 DWG. NO. D03